MUNICIPAL CORPORATION OF GREATER MUMBAI



Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.

1100



Master & Associates Architects, Interior Designer & Project Management Consultants **MUNICIPAL CORPORATION OF GREATER MUMBAI**

瞃



ANNEXURE – I PRICE VARIATION CLAUSE

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



Master & Associates Architects, Interior Designer & Project Management Consultants

79 Price Variation Clause

The Contractor shall be reimbursed or shall refund to the Corporation as he case may be thevariation in the value of the work carried out from time to time, depending on whether the prices of material and labour as a whole rise or fall, and the method adopted for such computations shall be as given below, it being clearly understood that the contractor shall have no claim for being reimbursed on the ground that the price of a particular material or group of materials have risen beyond the limits of the presumptions made in the following paras, however, no price variations shall be made applicable for contracts upto 12 months:

- A) Controlled materials: Price variations shall be permitted in respect of these materials the price level of which is controlled by the Government or its agency. The rate ruling on the date of submission of the tender shall be considered as the basic price of such material for adjustment. Any variation in this rate shall be considered for reimbursement to the contractor or refund to be claimed from the contractor as the case may be. The contractor shall, for the purpose of adjustment submit in original the relevant documents from the suppliers.
- B) Labour and other materials: For the purpose of this contract and for allowing reimbursement of refund on account of variation of prices of (i) labour, and (ii) materials other than materials mentioned in A above, computation will be based on the formula enunciated below which is based on the presumptions that :
- i) The general price level of labour, rises or falls in proportion to the rise or fall of consumer price index number 9 (general) for working class in Mumbai.
- ii) The general price level of materials rises or falls in proportion to rise or fall of wholesale price index as published by 'Economic Adviser to Govt. of India'.
- iii) And that the component of labour is to the extent of 30 percent of 88 percent and the component of materials is to the extent of 70 percent of 88 percent of the value of the work carried out. The remaining 12 percent being the presumptive profit of the contractor.
- a) Formula for Labour component:

$$VL = (0.88 \text{ R}) \times 30 \times (I - IO)$$

100 IO

b) Formula for Material component :

$$VM = (0.88 \text{ R x } 70 \text{ - C}) \text{ x } (W - WO)$$

$$100 \text{ WO}$$

Where -

- VL = Amount of price variation to be reimbursed or claimed as refund on account of general rise or fall of index referred to above.
- I = Consumer Price Index number of working class for Mumbai (declared by the Commissioner of Labour and Director of Employment, Mumbai) applicable to the period under reference (base year ending 2004-05 as 100 i.e. new series of indices).
- IO = Consumer price index number for working class for Mumbai (declared by the Commissioner of labour and Director of Employment, Mumbai) prevailing, on the day of 28 days prior to the date of submission of the tender.
- VM = The amount of price variation to be reimbursed or claimed as refund on account of general rise or fall of wholesale price index for period under reference.

- W = Average wholesale price index as published by Economic Adviser to Govt. of India applicable to the period under reference.
- WO = Wholesale price index as stated above prevailing on the day of 28 days prior to the date of submission of the tender.
- R = Total value of the work done during the period under reference as recorded in the Measurement Book excluding water charges and sewerage charges but including cost of excess in respect of item upto 50 percent
- C = Total value of Controlled materials used for the works as recorded in Measurement Book and paid for at original basic rate plus the value of materials used .
- i) The quantity of the Controlled material adopted in working out the value of 'C' shall be inclusive of permitted wastages as / if mentioned in specifications.
- ii) The basic rate for the supply of controlled material shall be inclusive of all the components of cost of materials excluding transport charges incurred for bringing the material from place of delivery to the site.

Computations based on the above formula will be made for the period of each bill separately and reimbursement will be made to (when the result is plus) and refund will claimed from (when the result is minus) the contractor's next bill. The above formulae will be replaced by the formulae in Annexure-I as and when mentioned in special conditions of contract

The operative period of the contract for application of price variation shall mean the period commencing from the date of commencement of work mentioned in the work order and ending on the date when time allowed for the work order and ending on the date when time allowed for the work specified in the contract for work expires, taking into consideration, the extension of time, if any, for completion of the work granted by Engineer under the relevant clause of the conditions of contract in cases other than those where such extension is necessitated on account of default of the contractor.

The decision of the Engineer as regards the operative period of the contract shall be final

and binding on the contractors.

- iii)Where there is no supply of controlled items to contractor the component 'C' shall be taken as zero.
- C) Adjustment after completion: If the Contractor fails to complete the works within the time for completion adjustment of prices thereafter until the date of completion of the works shall be made using either the indices or prices relating to the prescribed time for completion, or the current indices or prices whichever is more favorable to the employer, provided that if an extension of time is granted, the above provision shall apply only to adjustments made after the expiry of such extension of time.
- D) Price variation will be calculated similarly and separately for extra items and / or excess quantities and provisional sums calculated under Sub Clause 10 (b)A (i)&(ii) and Sub Clause 10 (b) B(ii) based on the above formula/formulae in Annexure-I as and when mentioned in Special conditions of contract; IO and WO being the indices applicable to the date on which the rates under Sub Clause 10 (a)A (i)&(ii) and Sub Clause 10 (a) B(iii) are fixed. No price variation shall be admissible for FAIR items created during execution.

80. Maximum Price Variation shall be as follows:

Time Period of Project	Maximum limit of Price Variation
Up to 12 months Above12 months to 24	No variation allowed 5%
months Above 24 months	10%

*Approval of AMC/MC shall be obtained before invitation of tender in case of any changes in above.

Note:1) The extension in time period for the projects originally estimated including monsoon results in change of price variation slabs as mentioned above i.e. from first slab to second slab or from second slab to third slab, then the maximum limit of original slab will prevail.

2) Operative period shall mean original or extended time period of contract.

For example:

Extension of Time period	Maximum Price Variation
If original period of 11 months including monsoon extends to 16. The operative period will be 11+5 months.	No variation allowed
If original period of 11 months excluding monsoon extends to 16. The operative period will be 11+5 months.	Maximum 5% variation allowed

Price Variation during Extended Period of Contract:

(i) Extension Due To Modification & Extension for delay due to MCGM : The price variation for the period of extension granted shall be limited to the amount payable as per the Indices. In case the indices increases or decreases, above/below the indices applicable, to the last month of the original or extended period vide clause8(l)(a)(i) and (ii) of standard GCC (ii) Extension Of Time For Delay Due To Contractor :

(a) The price variation for the period of extension granted shall be limited to the amount payable as per the Indices in case the indices increase, above the indices applicable, to the last month of the original completion period or the extended period vide above clause 8(1)(a)(i) and (ii) of standard GCC.

(b) The price variation shall be limited to the amount payable as per the indices, in case the indices decrease or fall below the indices applicable, to the last month of original / extended period of completion period vide above clause 8(l)(b) of standard GCC, then lower indices shall be adopted.

(iii) Extension of Time For Delay due to reasons not attributable to MCGM and Contractor (Reference Cl.8(d) of Standard GCC):

The price variation for the period of extension granted shall be limited to the amount payable as per the Indices in case the indices increases or decreases, above/below the indices applicable, to the last month of the original period.

MUNICIPAL CORPORATION OF GREATER MUMBAI



ANNEXURE – II SOIL INVESTIGATION REPORT

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



Master & Associates Architects, Interior Designer & Project Management Consultants



RELIABLE ENGINEERING

Office: - 304, Vastu Pooja CHS, Near Raut Chawl, Barrage Road, Kulgaon, Badlapur (West) Dist. - Thane 421503 Maharashtra (India) Email ID: - <u>reliableeng7@gmail.com</u> <u>reliablegeotechnic@outlook.com</u> _Contact: +91-9987193247 +91-9172214249

GEOTECHNICAL INVESTIGATION REPORT

GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI

> CLIENT M/s. MASTER AND ASSOCIATES

GEOTECHNICAL INVESTIGATION AND REPORT SUBMITTED BY M/s. RELIABLE ENGINEERING 304, VASTU POOJA BUILDING, NEAR RAUT CHAWL, BARRGAE ROAD, KULGAON, BADLAPUR (WEST) DIST-THANE 421503 EMAIL : reliableeng91@gmail.com reliableeng7@gmail.com +91-9987193247 +91-9172214249

REPORT NO. 095 DATED 16 August 2022



<u>GEOTECHNICAL INVESTIGATION REPORT</u> <u>PROPOSED REDEVELOPMENT</u> <u>ON PLOT KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO-1(PT), & CTS NO-3(PT), OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI</u> <u>FOR M/S MASTER AND ASSOCIATES</u>

Table of Contents

	ltem	<u>Page</u>
1.0	INTRODUCTION	1
2.0	EXPLORATION PROGRAM	1
	2.1 Exploration Scope2.2 Subsurface Conditions2.3 Groundwater Levels	1 2 3
3.0	FOUNDATION RECOMMENDATIONS	4
	3.1 Foundation Protection	5
4.0	FIELD EXPLORATION PROCEDURES	6
	ANNEXURES	7
	Figure 1: Borehole Location Plan Borehole Logs Subsurface Profile Laboratory Test Results References/Calculations	





<u>GEOTECHNICAL INVESTIGATION REPORT</u> <u>PROPOSED REDEVELOPMENT</u> <u>ON PLOT KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO-1(PT), & CTS NO-3(PT), OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI</u> <u>FOR M/S MASTER AND ASSOCIATES</u>

1.0 INTRODUCTION

M/s Master and Associates plan construction of redevelopment at CTS no-1(pt) & CTS no-3(pt), Deonar, Mumbai. The work of geotechnical investigation was awarded to Reliable Engineering. The fieldwork and laboratory tests for the geotechnical investigation were completed by Reliable Engineering in August 2022. This report prepared by Reliable Engineering presents the results of the geotechnical investigation along with foundation recommendations for the proposed redevelopment.

2.0 EXPLORATION PROGRAM

2.1 Exploration Scope

Two Boreholes (BH-1 and BH-2) were completed for the project as illustrated on the Borehole Location Plan in the Annexure.



2.2 Subsurface Conditions

The subsurface profile at this site generally consists of fill overlying residual soil underlain by completely weathered bedrock. Encountered soil/rock layers are described below;

LAYER I: FILL

Fill, consisting mostly of clay with boulders was encountered at the ground surface in the boreholes. The lower boundary of this layer was encountered at depths of 1.0m to 4.5m below the existing ground surface.

LAYER II: RESIDUAL SOIL

Residual soils, consisting mostly of brownish clay were encountered below fill layer in the borehole BH-01. Based on Standard Penetration Tests (SPT) conducted within this layer, consistency of cohesive soils (clay) was medium stiff. The lower boundary of this layer was encountered at a depth of 5.7m below existing ground surface.

LAYER III: BASALT BEDROCK

Basalt bedrock was encountered at a depth of 5.7m below existing ground surface. The bedrock was typically completely weathered. Core Recoveries varied of 20% to 30%, while Rock Quality Designation (RQD) was nil. The boreholes were terminated in this layer at a depth of 10.0m below the existing ground surface



2.3 Groundwater Levels

Groundwater accumulation in boreholes was monitored during and after the completion of drilling activities. Groundwater was observed in boreholes at a depth of 2.0m below existing ground level. Seasonal and annual fluctuations in groundwater levels can be expected.



3.0 FOUNDATION RECOMMENDATIONS

Foundation recommendations are provided in table A below;

TABLE A FOUNDATION RECOMMENDATIONS

BOREHOLE NUMBER	DEPTH OF FOUNDATION	SAFE BEARING CAPACITY (t/m²)	ALLOWABLE SETTLEMENT (mm)	MODULUS OF SUBGRADE REACTION (t/m ³)
	1.5m	12 t/m ²		480 t/m ³
BH-01	3.0m	15 t/m ²	25 mm	600 t/m ³
	4.5m	16 t/m ²		640 t/m ³
	5.7m	30 t/m ²	12 mm	2500 t/m ³
	1.5m (Fill)	5 t/m ²	0E rearea	200 t/m ³
BH-02	3.0m (Fill)	8 t/m ²	25 mm	320 t/m ³
	4.5m	30 t/m ²	12 mm	2500 t/m ³
Note: When	never foundations a	re placed on fill	minimum double la	aver of well

compacted rubble soling should be provided beneath the footings.

Excavation sides should be sloped at a maximum slope of 1:1 (horizontal: vertical) or flatter.

Uniformity in sub-stratum can be delineated upon completion of foundation excavations. It is recommended to verify subsurface soil stratum by experienced practicing geotechnical engineer before completion of footings/foundations.



3.1 Foundation Protection

Groundwater samples were collected for chemical analysis from the site. Results of Chemical analysis are enclosed in the Annexure. Based on chemical results, the site falls under Class I for sulphates and chlorides (As per IS456-2000 and as per CIRIA Special Publication No. 31). A 'Moderate' exposure condition was assigned to this site. Hence, following precautions shall be taken to protect concrete and reinforcement in foundations;

Type of Cement:	OPC or PPC
Minimum Grade of Reinforced Concrete:	M25
Minimum Cement Content for spread footings:	300 kg/m ³
Maximum Water Cement Ratio:	0.45
Minimum Cover to Reinforcement:	50mm



4.0 FIELD EXPLORATION PROCEDURES

The sub-surface investigation was completed generally as per IS: 1892-1979. The field investigation was carried out using a rotary machine. Casing was used to support sides of borehole until sufficiently stiff strata was encountered. Standard Penetration Tests (i.e. SPT) were carried out in soil in accordance with IS 2131-1981. Using this procedure, a 2" outside diameter split-barrel sampler is driven into the soil by 63.5 kg. weight falling through 75 cm height. After an initial set of 15cm, the number of blows required to drive the sampler an additional 30 cm, is known as the "penetration resistance" or "N value".

When SPT refusal was obtained in hard strata, rock coring was done using diamond bit and double tube core barrel to obtain rock samples. Percent Rock Core Recovery and Rock Quality Designation (%RQD) were determined. % RQD = $100 \times \text{Sum of length of rock}$ pieces in cms, each having lengths greater than 10cms/Total length of core run.

Sincerely,

Reliable Engineering.

THOER P.B

R. Jagadale B.E (Civil) M.Tech (Geotechnical)



REFERENCES

- 1) Foundation Analysis and Design, J.E. Bowles, McGraw Hill Publication, 5th Edition, 1996.
- 2) Canadian Foundation Engineering Manual.
- 3) Soil Mechanics in Engineering Practice, 2nd Edition, Terzaghi K. and Peck R. B., John Willey and Sons, 1967.
- 4) Foundation Design Manual, N. V. Nayak, 5th Edition, 1996.
- 5) IS:6403-1981, Code of Practice for Design and Construction of Shallow Foundations on Soils.



SAMPLE CALCULATION OF ALLOWABLE BEARING CAPACITY FOR FOUNDATIONS ON COMPLETELY WEATHERED BEDROCK

_____ GL +0.0m Layer I, Fill

_____ -1.0m to -4.5m

Layer II, Residual Soil SPT N Value: 16

_____ -4.5m to -

5.7m

Layer III, Completely Weathered Bedrock

(Assuming Completely weathered Bedrock to be a very dense granular soil.)

Net Ultimate Bearing Capacity = q_u = cNc s_c + q (N_q - 1) s_q + 0.5 B $\gamma N \gamma s_{\gamma}$ (Refn. 5, Table 4-1)

Where,

- q = Overburden Pressure (i.e. submerged unit weight x depth of foundation)
- c = Cohesion
- B = Minimum Width of foundation = 1m
- γ' = submerged unit weight of soil = 0.80

 N_c , N_q , N_{γ} = Terzaghi's Bearing capacity factors

- Sc, sq, s_{γ} = Shape factors = Conservatively assumed as 1, 1, and 0.6
 - D = Depth of Footing = 4.5m

Minimum SPT N value obtained in boreholes = 50 Corresponding friction angle = 42° (Reference No. 5) Corresponding Nc=100, Nq=92, N_y=174 (Reference 5, IS:6403-1981);

Substituting these values in the above equation; q ultimate =q_u =[0x100x1]+[4.5x0.8x(92-1)x1]+[0.5x1x0.8x174x0.6]= 0+328+42 = 370 t/m² q safe = q_u/F.S. = 370/3 = 123 t/m²

Restricted to 30 t/m² to limit settlement as shown below.



CALCULATION OF SETTLEMENTS OF FOUNDATIONS (3M X 3M) EXERTING PRESSURE OF 30 T/M2:

From Reference No. 1:

Settlement =
$$S = q_0 B' \frac{1 - \gamma^2}{E_s} m I_s I_f$$

Where,

 $\begin{array}{l} q_0 = Footing \mbox{ Pressure} = 30 \ t/m^2 \\ B' = B/2 \ (Where B is the width of pressure distribution \\ \mu = Poisson's \ ratio = 0.3 \\ E = Modulus \ of \ Elasticity \\ I_s = Influence \ Factor \ (Obtained \ from \ Table \ 5-2, \ Reference \ No. \ 1) \\ I_f = Depth \ Factor \ (Obtained \ from \ Figure \ 5-7, \ Reference \ No. \ 1) \\ m = 4 \ for \ center \ of \ footing \end{array}$

Very conservatively assuming completely weathered bedrock to be overconsolidated sand:

E value for over-consolidated sand = 105(N)+4000 (Reference No. 1) Therefore, for a SPT N value of 50, E=9250 t/m²

L' = 3/2 = 1.50, B' = 3/2 = 1.5, H=6m, and D=5.7m Therefore, M=L/B=1; and N=H/B'=4, and D/B=1.9 Corresponding, I_s = 0.43, Conservative I_f = 1 (From Table 5-2, Reference 1)

Settlement of Layer = $S_1 = 30x1.5x(1-0.3x0.3)x4x0.43/9250 = 0.0076m = 7.6mm$

ANNEXURE

LOCATION MAP



BOREHOLE LOGS

	CLIENT M/s. MASTER AND ASSOCIATES PROJECT GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI														BH NO. SHEET NO.					01 1 of	1
LOC	ATION	: -				D	ATE			: 1	1-08	8 -202	2 TO	12-0	8-20	22					
	ORDINAT		-				ETH						DRILI								
	OUND R.L.					C	ASIN	IG		: 5	.00	MTR	NX C	ASI	NG						
GRC	OUND W.T	. : 2	2.00 MTR BELOW G.L.																		
DEPTH (m.)	DIA. OF BORE HOLE	LOG.	STRATA DESCRIPTION	DEPTH (m)	Elevation (m)	TYPE OF SAMPLE	15cm 1	BLO 15cm	WS 15cm 1	I5cm	SPT N	C R %	RQD %	Gravels %	Sand %	Silt %	Clay %	Liquid Limit %	Plastic Limit %	Plasticity index	UCS kg/cm2 PL
- - 1.00	Pit Excavation		Backfilled Soil consisting of FILL	1.00																	
-	Ехсау Р		Brownish Stiff Silty CLAY	1.50		DS															
2.00			with sand particles	2.10		SPT1	06	06	07	09	13										
- - <u>3.00</u>				3.00																	
- - 4.00	100 MM		Dark Brown stiff Silty CLAY with sand particles	3.60		SPT2	04	05	05	80	10										
-				4.50																	
5.00				5.10		SPT3	04	06	06	07	12										
- - 6.00				5.70								20	NIL								
-				0.00																	
	NX size			7.50								24	NIL								
			Gray Highly weathered Fractured BASALT Rock									30	NIL								
9.00				9.00																	
- - 				10.00								30	NIL								
SPT N = STANDARD PENETRATION TEST VALUE RQD = ROCK QUALITY DESIGNATION UDS = UNDISTURBED SOIL SAMPLE UCS = UNCONFINED COMPRESSIVE STRENTGH CR = CORE RECOVERY DS = DISTURBED SOIL SAMPLE VST = VANE SHEAR TEST PL = POINT LOAD												ENTGH									
		E	REMARKS : BH-01 is termin RELIABLE ENGINEERII 304, VASTU POOJA BUID CHAWL, BARRAGE ROAL BADLAPUR WEST, DIST-1 Email ID reliablegeotechr	ated at 10 NG ING, NEA D, KULGA FHANE (M nic @outlo	.00 mtr be R RAUT ON, I.H.) 4215	elow G.L. 503 +91-9	987	193	247	,	TY TY RE DF	'PE OF EFEREI RILLING	PL = BARRE BIT = N NCE ST G MACH BY : R	EL = D IX DIA ANDE IINE =)OUBI AMON ERD = = (CAL	LE TUI D BIT IS 189 .YX, 8	92-197 HP E	NGINI	-	BN	O. 095
			reliableeng7@gn	nan.com		+91-9	1722	214	249	'		,				· · · · //-//	17 JOA		50	5 140	2.000

CLIE	CLIENT : M/s. MASTER AND ASSOCIATES PROJECT : GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT,													BH NO.					: 02				
PRO	JECT			EOTECHNICAL INVESTIGATION FO																	: 02 : 1 of 1		
				OF VILLAGE-DEONAR IN M/E WAR			. 1(pt) d																
LOCATION : DATE : 13-08-2022 TO CO-ORDINATES : METHOD : ROTARY DRILL														22									
			S:					ETH ASII						DRILL NX C									
				.10 MTR BELOW G.L.				ASI	NG			.00			ASI	NG							
								-										1	-			_	
DEPTH (m.)	DIA. OF BORE HO		LOG.	STRATA DESCRIPTION	DEPTH (m)	Elevation (m)	TYPE OF SAMPLE	15cm		WS 15cm	15cm	SPT N	C R %	RQD %	Gravels %	Sand %	sit %	Clay %	Liquid Limit %	Plastic Lim %	Plasticity index	UCS kg/cm2	2
- - <u>1.00</u> -	Excavation				1.50		DS																
 2.00 				Backfilled Soil consisting of FILL	2.10		SPT1	04	03	05	05	08											
- 3.00	-				3.00																		
-	100 MM				3.60		SPT2	04	04	04	05	08											
					4.50		SPT3	25	E 2														
- 			$\begin{array}{c} \hline 7 \\ \bigtriangledown \\ \hline 7 \\ \bigtriangledown \\ \hline \\ \hline \\ \hline \\ 7 \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline \\ \hline$		4.70		3613	23	<u>52</u>			<u> </u>	21	NIL									
- 	-		7		6.00																		
- - <u>7.00</u> -	NX size		7		7.50								22	NIL									
 <u>8.00</u> 	-		7	Grayish Brown Highly weathered BASALTIC BRECCIA Rock									28	NIL									
9.00			7∇ $\nabla \nabla$ 7∇		9.00																		
- _ 10.00					10.00								29	NIL									
	=STANDAF			TION TEST VALUE RQD = ROCK G		SIGNATION	UDS =	UND	ISTU	JRBE	D SC	DIL SA	MPLE	UCS	4U = 6		FINE		/ IPRE	SSIVE	STR	ENTG	j. H
REMARKS : BH-02 is terminated at 10.00 mtr below G.L. RELIABLE ENGINEERING 304, VASTU POOJA BUIDING, NEAR RAUT CHAWL, BARRAGE ROAD, KULGAON, BADLAPUR WEST, DIST-THANE (M.H.) 421503 Email ID reliablegeotechnic@outlook.com +91-9987193247											PL = BARRE BIT = N NCE ST G MACH	= POII EL = D IX DIA ANDE IINE =	NT LO OUBL AMON ERD = = (CAL	AD LE TU D BIT IS 18 LYX, 8	BE 92-19 HP E	79 NGINI	Ε).		D. 09				
				reliableeng7@gmail.com +91-9172214249										א.ים.	ULIN		, wiAl	IAJA	4 N	50	אים	J. US	,0

SUBSURFACE SOIL PROFILE



LABORATORY TESTS



SOIL TEST DATA SHEET IS 2720 Part 4, 5, 6 PROJECT : GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI

CLIENT: M/s. MASTER AND ASSOCIATES

																					DATE:	16-08	8-2022
ö	. <u>=</u>	U	Density cr	gm/ m ³	ontent,	n (I.S)	N	lechanic	al Analy	sis		Consista	ancy Lim	its	Shear	Strengt	h Test	ression 2	ex		rical lidation	ity	
Bore Hole No.	Depth m.	Sample Type UD / D	Wet Density	Dry Density	Natural Moisture Content, w %	Soil Classification (I.S)	Gravel %	Sand %	Silt %	Clay %	Liquid %	Plastic %	Plasticity Index, I _p %	Shrinkage Limit %	Shrinkage Ratio	Cohesion C _u kg/cm ²	Degree f	Unconfined Compression Test Kg/cm ²	free swell index	Comp. Index C _{cv} (Lab)	Initial Void Ratio	Specific Gravity	Remarks
BH-01	1.50-2.10	SPT 1				СН	0	18	8	2	62	24	38										
BH-01	3.00-3.60	SPT 2				СН	0	21	7	'9	59	22	37										
CHEM :	Chemical Analysis		Tuu :	Triaxial Tes	st (Unconso	lidated Undra	ained)			SP :	Swelling	Pressure	or Swelli	ng Potent	tial Test				f :	Angle of Int	ternal Friction	1 1	
COMP :	Compaction Test		Tcu :	Triaxial Tes	st (Consolida	ated Undrain	ied)			SPT :	Standard	d Penetra	tion Test	Sample					Cc :	Undrained	Cohesion		
DS :	Direct Shear		Tcd :	Triaxial Tes	st (Consolida	ated Drained)			UDS :	Undistu	irbed So	il Sample	2					f' :	Effective A	ngle of Interr	al Friction	
к :	Permeability Test		NP :	Non Plastic	:								Shear Tes						Cc':	Effective Co	ohesion		
FSI :	Free Swell Test		SL :	Shrikage Li	mit Test					UC :	Unconfir	ned Comp	pression T	est					>:	Combined	Silt + Clay		
			·					GEC) EN	GIN	EERS	5, КA	ALYA	N									

16-08-2022

				TES	T RES	SULTS	5 OF	ROCK CO	ORES	As per IS	9143, 8	764, 13	3030			
CLIEN	T:	M/s. M	ASTER AND ASSO	CIATES												
PROJE	PROJECT: GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PROJECT: PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI 16-08-2022															
Sr. No.	Bore Hole No.	Core No.	Depth, m	Diameter, cm	Height, cm	H : D (1:H/D)	Correction Factor	Condition of Test	Failure Load	Uniaxial Compressive Strength	Point load index	Porosity	Water Absorption	Dry Density	Specific Gravity	Remark
				cm	cm		Ō	Co	kN	kg/cm 2	kg/cm 2	%	%	gm/cm	S	
1	BH-01	4	6.00-7.50	5.41	6.21	1.15	0.86	Soaked	1.6		6	3.03	1.12	2.70		
2	BH-02	8	4.70-6.00	5.42	6.35	1.17	0.86	Soaked	1.1		4	3.70	1.39	2.66		
				I	I	GEO	ENG	INEERS, I	KALYA	N	I		I	<u> </u>		

	CHEMICAL TEST RESULT OF GROUND WATER SAMPLES. As per IS 3025 Part 11, 24, 32													
CLIENT: PROJECT:			DPOSED REDEVELOP		OWN AS "600 TENEM	DATE ENT PLOT" BEARIN	16-08-2022 G CTS NO. 1(pt) & CTS							
SR NO.	BH NO.	DEPTH IN METERS	TYPE OF SAMPLE	pH ELECTROMETERIC ALLY * Limit between 6.3 to 8.5	SULPHATE AS SO ₃ ppm * Limit <400ppm Maximum	CHLORIDE AS CI ppm * Limit <2000ppm Maximum	REMARKS							
1	BH-01	2.00	Water	6.52	165	305								
	GEO ENGINEERS, KALYAN													

PHOTOS

CLIENT: M/s. MASTER AND ASSOCIATES

PROJECT: GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI

BH-1



CLIENT: M/s. MASTER AND ASSOCIATES

PROJECT: GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI

BH NO. - 01

BOX NO. 01 OF 01

DEPTH 0.00 TO 10.00 MTR.



DRILLING CONTRACTOR: RELIABLE ENGINEERING, BADLAPUR +91-9987193247 +91-9172214249 reliableeng7@gmail.com

CLIENT: M/s. MASTER AND ASSOCIATES

PROJECT: GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI

BH-2



CLIENT: M/s. MASTER AND ASSOCIATES

PROJECT: GEOTECHNICAL INVESTIGATION FOR PROPOSED REDEVELOPMENT ON PLOT, KNOWN AS "600 TENEMENT PLOT" BEARING CTS NO. 1(pt) & CTS NO. 3(pt) OF VILLAGE-DEONAR IN M/E WARD IN MUMBAI

BH NO. – 02

BOX NO. 01 OF 01

DEPTH 0.00 TO 10.00 MTR.



DRILLING CONTRACTOR: RELIABLE ENGINEERING, BADLAPUR +91-9987193247 +91-9172214249 reliableeng7@gmail.com **MUNICIPAL CORPORATION OF GREATER MUMBAI**



ANNEXURE – III CONTOUR SURVEY PLAN

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



Master & Associates Architects, Interior Designer & Project Management Consultants
ANNEXURE - III



N 2108275 N 2108270 N 2108270			$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
N 2108265 N 2108260			$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
N 2108255 N 2108250			
N 2108245 N 2108240			
N 2108235 N 2108230			$\begin{array}{c ccccccccccccccccccccccccccccccccccc$
N 2108225 N 2108220 N 2108220			
N 2108215 N 2108210			
N 2108205 N 2108200 N 2108200			
N 2108195 N 2108190			
N 2108185 N 2108180			
N 2108175 N 2108170			
N 2108165 N 2108160			
N 2108155 N 2108150			
N 2108145			
N 2108135			
N 2108115 N 2108110 N 2108110			
N 2108100 N 2108100 N 2108100			
N 2108095 N 2108090 N 2108090			
N 2108075			
N 2108070 N 2108065 N 2108065 N 2108065 N 2108066			
N 2108060 N 2108055 N 2108055 N 2108050 O S S S S S S S S S S S S S S S S S S S		5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	01
N 2108045 3^{N}		A A A A A A A A	BOXCULVERT2X5.5X2I
N 2108040 00 00 00 00 00 00 00 00 00 00 00 00		SPAN SPAN Road Level (m	2 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
N 2108030 N 2108025 N 21080 N 210802 N 2108025 N 2108025 N 2108025 N 2108025 N 210802		ny si	m) 3.075
N 2108020 N 2108015 N 2108015			
N 2108010 N 2108005			
N 2108000 N 2107995			
N 2107990 N 2107985			
N 2107980 N 2107975 N 2107975			
N 2107970 N 2107965 N 2107965			
N 2107960 N 2107955 N 2107955			
N 2107950 N 2107945 N 2107945			
N 2107940 N 2107935 N 2107935			
N 2107930 + + + + + + + + + + + + + + + + + + +	$\begin{array}{c} - \varepsilon \\ - \varepsilon \\$		E 281335 E 281335 E 281325 E 281305 E 281290 E 281290 E 281290 E 281290 E 281290 E 281290 E 281290 E 281290 E 281290
ਯੁੱਠ ਯੁੱਠ ਯੁੱਠ ਯੁੱਠ ਯੂੱਠ ਯੂੱਠ ਯੂੱਠ ਯੂੱਠ ਯੂੱਠ ਯੂੱਠ ਯੂੱਠ ਯੂ	SURVEY PI SCALE=1:1000		ဝဟဝဲဟ်ဝိတ်ဝိတ်ဝတ်ဝိတ်ဝိတ်
NOTES-: 1. ALL DIMENSION IN METER. 2. ONLY WRITTEN DIMENSION SHOULD BE FOLLOWED ROAD EDGE	CLIENT:-		PROJECT:- Proposed redevelopment on open plot, know as 600 tenement plot bearing CTS No. 1(pt) & CTS No 3(pt) of village Deonar in M/East Ward in Mumbai
2. ONLY WRITTEN DIMENSION SHOULD BE FOLLOWED. ROAD CENTER 3. ALL COORDINATES ARE w.r.t. DGPS 1. THE ASSUMED CO-ORDINATES DRAIN TOP OF DGPS 1. ARE EAST=281253.110 NORTH=2108323.216 NALLAH A TRM FOLL OWED ON PORCE AND ADDRESSING CONTRACT OF THE ASSUMED CO-ORDINATES NALLAH	ELECTRIC BOX Image: Constraint of the second seco	40001 Sector-34, Navi Mumbai - 410 209, T : +91-22-6560	TITL F:- Detailed Topographic Survey for Open Plot
5. SURVEY PERIOD =05.12.2020 TO 07.12.2020 TOILET	WATER TANK NAM GATE COMPOUND WALL MANHOLE CHECKED BY:- CONTOUR APPROVED BY:-	E SIGNATURE NAME S DRAWN BY:- CHEAKED BY:-	IGNATURE DWG. NO. Survey Plan 01 SCALE:- 1:1000 SHEET SIZE : A 2 DATE :10.12.2020
CIRCLE O SHED O	DATE :-	APPROVED BY:-	DWG.ADD.1/D /103 Topographic Survey Lonavala



ANNEXURE – IV CLUBHOUSE AREA

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.





7	SAUGHTER HOUSE		S Marcala Court Court Court	
	TION PLAN SC NT OF SHEET	ALE 1:4000	Arrente Arrent	Pay Ground
CLUB F	IOUSE FLOOR	PLAN		
AE	D-FO	D-FO	ום	(-CFO
SE	-BP	AE-BP	EE	-BP
F	BY THE ARCHITEC ROVISION THEREFO	HAT THE SCOPE OF WORK T / CONSULTANT AND CO DRE I AM SATISFIED WITH	INSIDERING THE E	BUDGET ROPOSAL"
NOTE HENCE I RE	: USER SIGNATURE I IS REQUESTED TH QUIRED , THE SAME	IS PROVIDED IN THE SCA IAT THE SAME IS NOT INS WILL BE OBTAINED BEFO	INNED COPY OF T ISTED ON DIGITAL DRE STARTING OF	HE PLANS / PRINTS, IN THE WORK
			AC	C-Estate
ARCHI	TECT MASTER & AS	SSOCIATES MUNI	CIPAL ARCHI	TECT
1				
	_			
R0 REVISION	DATE		RIPTION 2023/RESIDENT	BY
FILE PA	DATE ATH : PC:03\G: PROJECT MOTHER DF DWG : DVAL DRAWING	DESCF AR. PRATIKSHA 2021- S\1896-600 TENEMEN EARTH BP COMMENT	2023\RESIDENT ITS\R7- RG REA	IAL
REVISION FILE PA TYPE C APPRC CLIENT BRIHAN	DATE ATH : PC:03\G:\ PROJECT MOTHER DF DWG : DVAL DRAWING -: NMUMBAI MUI	DESCF AR. PRATIKSHA 2021- S11896-600 TENEMEN EARTH BP COMMENT G	2023\RESIDENT ITS\R7- RG REA	BY TAL
REVISION FILE PA TYPE C APPRC CLIENT BRIHAN TITLE C PROPOS ON OPE CTS NO WARD II	DATE PC:03(6): PR:0405 PR:0405 PR:0405 PR:0405 PDF DWG : VVAL DRAWING PF DRAWING : SED REDEVELI N PLOT,KNOW 1 (PT) & CTS H MUMBAI	DESCF AR. PRATIKSHA 2021- S\1896-600 TENEMEN EARTH BP COMMENT	2023/RESIDENT ITS/R7- RG REA ATION (BMC) OR PLAN CIPAL STAFF ENTS PLOT BI	UUARTE
REVISION FILE PA TYPE C APPRC CLIENT BRIHAN TITLE C ON OPE CTS NO WARD II JOB TIT	DATE PC:03(6): PR:0405 PR:0405 PR:0405 PR:0405 PDF DWG : VVAL DRAWING PF DRAWING : SED REDEVELI N PLOT,KNOW 1 (PT) & CTS H MUMBAI	DESCF AR. PRATIKSHA 2021- IS 19896-000 TENEMEN EARTH BP COMMENT 3 NICIPAL CORPORA CLUB HOUSE FLO OPMENT OF MUNIC (N AS '600 TENEME 10. 3(PT) OF VILLA	2023/RESIDENT ITS/R7- RG REA ATION (BMC) OR PLAN CIPAL STAFF ENTS PLOT BI	QUARTE
REVISION FILE PA TYPE C APPRC CLIENT BRIHAT TITLE C PROPOS ON OPE CTS NO WARD II JOB TIT DRAWN	DATE TH : PC:03(G): PROJECT MOTHER PT DVG : VAL DRAWING : VAL DRAWING : SED REDEVELU SED REDEVELU N PLOT, KNOW A (PT) & CTS N N MUMBAI LE :	DESCF AR. PRATIKSHA 2021- IS 19896-000 TENEMEN EARTH BP COMMENT 3 NICIPAL CORPORA CLUB HOUSE FLO OPMENT OF MUNIC (N AS '600 TENEME 10. 3(PT) OF VILLA	2023/RESIDENT ITS/R7- RG REA ATION (BMC) OR PLAN CIPAL STAFF ENTS PLOT BI GE DEONAR	QUARTE EARING IN M/EAS
REVISION FILE PA TYPE C APPRC CLIENT BRIHAN TITLE C ON OPE CTS NO WARD II JOB TIT DRAWN CHECK	ATTE DATE PROJECT PROJECT MOTHER PF DWG :: VAL DRAWING : VAL DRAWING : SED REDEVELI SED REDEVELI N PLOT, KNOW . 1 (PT) & CTS N MUMBAI LE : I BY : PRATIKSH	DESCF AR. PRATIKSHA 2021-1 SI1989-600 TENEMEN EARTH BP COMMENT 3 NICIPAL CORPORA CLUB HOUSE FLO OPMENT OF MUNIC (N AS '600 TENEME NO. 3(PT) OF VILLA	ATION (BMC) OR PLAN CIPAL STAFF ENTS PLOT BI GE DEONAR	QUARTE EARING IN M/EAS CODE: 1
REVISION FILE PA TYPE C APPRC CLIENT BRIHAN TITLE C PROPOS ON OPE CTS NO WARD II JOB TIT DRAWN CHECK	DATE PROJECT MOTHER MOTHER MOTHER VAL DRAWING WMUMBAI MUI DF DRAWING : SED REDEVELI N PLOT, KNOW 1 (PT) & CTS N MUMBAI LE : I BY : PRATIKSH ED BY : UDM	DESCF AR. PRATIKSHA 2021- IS 1989-600 TENEMEN EARTH BP COMMENT 3 NICIPAL CORPORA CLUB HOUSE FLO OPMENT OF MUNIC IN AS '600 TENEME 40. 3(PT) OF VILLA IA IA IA	ATION (BMC) OR PLAN CIPAL STAFF DRAU	QUARTI EARING IN M/EA: CODE: NO: 189
REVISION FILE P/ TYPE C APPRC CLIENT BRIHAT TITLE C PROPO: ON OPE CTS NO ON OPE CTS NO CHECK SCALE: THIS	DATE DATE PROJECT MOTHER POWG: WAL DRAWING POWG IN MUMBAI MUI PE DRAWING IN SED REDEVELI SED REDEVELI SED REDEVELI SED REDEVELI BY : PRATIKSH ED BY : UDM AS MENTIONE DRAWING IS TH MASTER & ASS MACHTERIA REPRODU	DESCF AR. PRATIKSHA 2021- SI1986-600 TENEMEN EARTH BP COMMENT S NICIPAL CORPORA CLUB HOUSE FLO OPMENT OF MUNIC (N AS '600 TENEME NO. 3(PT) OF VILLA DOPMENT OF MUNIC N AS '600 TENEME NO. 3(PT) OF VILLA DOPMENT OF MUNIC N AS '600 TENEME DOPMENT OF MUNIC DOPMENT OF MUNIC DOPMENT OF MUNIC DOPMENT OF MUNIC N AS '600 TENEME DOMESTICATION OF VILLA TO DOMESTICATION OF VILLA DOPMENT OF MUNICIPAL DOPMENT OF MUNI	ATION (BMC) OR PLAN CIPAL STAFF DRAUNS (DAL STAFF DRAUNA DRAUNING REVISION	QUARTE EARING IN M/EAS CODE: 1
REVISION FILE P/ TYPE C APPRCC CLIENT TITLE C PROPO: ON OPE BRIHAY TITLE C PROPO: ON OPE NO PROPO: ON OPE RIHAY TITLE C CHECK SCALE:	DATE DATE PROJECT MOTHER MOTHER MOTHER MOTHER DVAL DRAWING SED REDEVELI N PLOT, KNOW 1 (PT) & CTS N MUMBAI LE: I BY : PRATIKSH ED BY : UDM AS MENTIONE DRAWING IS TH MASTER & AS: MASTER & AS: MAS	DESCF AR. PRATIKSHA 2021-1 SIS1989-600 TENEMEN EARTH BP COMMENT SILLIPAL CORPORA CLUB HOUSE FLO OPMENT OF MUNIC IN AS '600 TENEME NO. 3(PT) OF VILLA IN AS '600 TENEME NO. 3(PT) OF VILLA DATE : 17.01.202 HE PROPERTY OF SOCIATES IOSBACHAR COMMENTAR C	ATION (BMC) OR PLAN CIPAL STAFF DRAUNS (DAL STAFF DRAUNA DRAUNING REVISION	QUARTE ARING CODE: NO: 189 NO: R0



ANNEXURE –V GRIEVANCE CIRCULAR

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



ANNEXURE - V

MUNICIPAL CORPORATION OF GREATER MUMBAI

Central Purchase Department

CIRCULAR

No. D.M.C./CPD/3217 Date: 02.03.2019

Sub : To incorporate new clause of internal "GRIEVANCE REDRESSAL MECHANISM" in the standard Bid document.

Ref: i) CA/FRD/I/05 dt. 10.05.2016 ii) MGC/F/8155 dtd. 30.01.2019.



INTERNAL GRIEVANCE REDRESSAL MECHANISM



M.C.G.M. has formed a internal Grlevance Redressal Mechanism for redressal of bidder's grievances. Any Bidder or prospective Bidder aggrieved by any decision, action or omission of the procuring entity being contrary to the provisions of the tender or any rules or guldelines issued therein, in Packet 'A', 'B' & 'C' can make an application for review of decision of responsiveness in Packet 'A', 'B' & 'C' within a period of 7 days or any such other period, as may be specified in the Bid document.

While making such an application to procuring entity for review, aggrieved bidders or prospective bidders shall clearly specify the ground or grounds in respect of which he feels aggrieved.

Provided that after declaration of a bidder as a successful in Packet 'A' (General Requirements), an application for review may be filed only by a bidder who has participated In procurement proceedings and after declaration of successful bidder in Packet 'B' (Technical Bid), an application for review may be filed only by successful bidders of Packet 'A'. Provided further that, an application for review of the financial bid can be submitted, by the bidder whose technical bid is found to be acceptable /



responsive.

Scanned with

CamScanner

Upon receipt of such application for review, M.C.G.M. may decide whether the bid process is required to be suspended pending disposal of such review. The M.C.G.M. after examining the application and the documents available to nim, give such reliefs, as

Scanned by CamScanner

ANNEXURE - V

1

may be considered appropriate and communicate its decision to the Applicant and interview required to other bidders or prospective bidders, as the case may be.

M.C.G.M. shall deal and dispose off such application as expeditiously as possible and in any case within 10 days from the date of receipt of such application or such other period as may be specified in pre-qualification document, bidder registration document or bid documents, as the case may be.

Where M.C.G.M. fails to dispose off the application within the specified period or f the bidder or prospective bidder feels aggrieved by the decision of the procuring entity, such bidder or prospective bidder may file an application for redressal before the 'Internal Procurement Redressal Committee' within 7 days of the expiry of the allowed time or of the date of receipt of the decision, as the case may be. Every such application for internal redressal before Redressal Committee shall be accompanied by fee of Rs.25,000/- and fee shall be paid in the form of D.D. in favour of M.C.G.M.

1st Appeal by the bidder against the decision of C.E./HoD/Dean can be

made to concerned D.M.C / Director who should decide appeal in 7 days. If not satisfied, 2nd Appeal by the bidder can be made to concerned A.M.C for decision.

Grievance Redressal Committee (GRC) is headed by concerned D.M.C / Director of particular department for the first appeal / grievances by the bidder against the decision for responsiveness / non-responsiveness in Packet 'A', Packet 'B' or Packet 'C', and if not satisfied, concerned A.M.C. will take decision as per second appeal made by

This Grievance Redressal Committee (GRC) will be operated through DMC(CPD) office where appeals of aggrieved bidder will be received with fee of Rs. 25,000/- from aggrieved bidder. The necessary correspondence in respect of said applications to the aggrieved bidder & concerned department, issuing notices, arranging of Grievance Redressal Committee (GRC) with D.M.C and further proceeding will be carried out through registrar appointed by MCGM. No application shall be maintainable before the redressal Committee in regard of any decision of the M.C.G.M. relating to following issues: Determination of need of procurement The decision of whether or not to enter into negotiations.

Cancellation of a procurement process for certain reasons. On receipt of recommendation of the Committee, It will be communicated his decision thereon to the Applicant within 10 days or such further time not exceeding 20 days, as may be considered necessary from the date of receipt of the recommendation and in case of non-acceptance of any recommendation, the reason of such non-

Scanned with CamScanner

CS

ANNEXURE - V

Additional Municipal Commissioner and/or Grievance Redressal Committee, if found, come to the conclusion that any such complaint or review is of vexations. frivolous or malicious nature and submitted with the Intention of delaying or defeating any procurement or causing loss to the procuring entity or any other bidder, then such complainant shall be punished with fine, which may extend to Five Lac rupees or two percent of the value of the procurement, whichever is higher.

 All head of department are therefore requested to take a note of above and process tenders accordingly.

> Sd/- 21.02.19 D.M.C(CPD)

CIRCULAR

2018-19 No. D.M.C./CPD/3217 Date: 02.03.2019

CC: to

Director(E.S&P)

D.M.C(E)

D.M.C(S.E)

D.M.C(SWM)

D.M.C(Education)

	D.M.C(Vig.)	D.M.C(Z-I)	D.M.C(Z-II)	D.M.C(Z-111)	D.M.C(Z-IV)	1
	D.M.C(Z-V)	D.M.C(Z-VI)	·D.M.C(Z-VII) ···	- D.M.C(A&C)	D.M.C(Improvement)	(
	D.M.C(D.M)	D.M.C(Spl.)	D.M.C(M.C's Office)	D.M.C(E.R.)	Director(M.E & M.H)	
	Ch.M.S(Sp. Hosp.) Dean (KEM Hosp.)	E.H.O Dean (LTMG Hosp.& Med. College)	P.S. to M.C. Dean (B.Y.L Nair Hosp.)	C.E. Dean (Nair Hosp. Dental College)	P.S: to AMC(P)/ws/25	ci'
	Ch.E.(D.P)	Ch.E.(Roads & Traffic)	Ch.E.(M.S.D.P)	Ch.E.(SWD)	Ch.E.(S.O)	
	Ch.E.(S.P)	Ch.E.(W.S.P)	Ch.E.(Vig.)	Ch.E.(B.M)	Ch.E.(S.W.M)	
	Ch.E.(Bridge)	Ch.E.(M&E)	Ch.E.(C.T.I. & R.C)	Ch. L.O	Edu. Officer	3
	M.A	Security Officer	Law Officer	Supt. Of Garden	Supt. Of Licence	
\sim	M.C.A	M.S.	C.A:(F).	C.A.(T)	C.A.(W.S.S.D)	
5)	····	Copy	submitted for informa	tion please		

• ी जन्म ्य PY.CA (Exp) 1/4-1 02/02/17 DY Ch.E. (CPD) יייי יאונת אוני लेखा अधिकारी (अवज्य] था 2 Scanned by CamScanner Scanned with CamScanner



ANNEXURE –VI SCRUTINY FEE CIRCULAR

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



बहन्मुंबई महानगरपालिका

् परिपत्रक २०२३-२०२४

क्र. सीए/एफआरजी/ १० दिनांक १९.१०.२०२३

विषय :- महानगरपालिकेच्या विविध खात्यांमार्फत मागविण्यात येणा-या अनस्टार दरपत्रिका/ निविदा/दरपत्रिका/ ई-दरपत्रिका/ ई-निविदा दस्तऐवजांच्या छाननी शुल्काबाबत

संदर्भ :- १) प्रले/एफसीई/२८ दि. १३.०१.२०२३

२) परिपत्रक क्र. सीए/एफआरजी/२१ दिनांक ०८.०२.२०२३

३) एमजीसी/एफ/९५८५ दि. ११.०५.२०२३

४) परिपत्रक क्र. सीए/एफआरजी/०३ दिनांक ११.०५.२०२३

५) अति.आ./प्रकल्प/१३५१ दि. २३.०५.२०२३

६) परिपत्रक क्र. सीए/एफआरजी/०४ दि. २४.०५.२०२३

बृहन्मुंबई महानगरपालिकेच्या विविध खात्यांमार्फत मागविण्यात येणाऱ्या अनस्टार दरपत्रिका/निविदा/दरपत्रिका/ ई-दरपत्रिका/ई-निविदा दस्तऐवजांकरिता छाननी शुल्क आकारण्याबाबत उपरोक्त संदर्भ क्र. ४ व ६ अन्वये परिपत्रक निर्गमित करण्यात आले होते. परिपत्रक क्र. सीए/एफआरजी/०३ दिनांक ११.०५.२०२३ मध्ये पुढील प्रमाणे निर्देश देण्यात आले आहेत.

"सर्व खाते प्रमुख/सहाय्यक आयुक्त/रुग्णालय प्रमुख, अधिष्ठाता यांनी त्यांच्या अखत्यारीतील संबंधित कर्मचारीवृंदाना उपरोक्त सुचनेची काटेकोरपणे अंमलबजावणी करण्याचे तसेच मंजुरीच्या दिनांकापासून मागविण्यात येणाऱ्या अनस्टार दरपत्रिका/ निविदा/ दरपत्रिका/ ई-दरपत्रिका/ई-निविदा दस्तऐवजांकरीता निविदा शुल्क न आकारता सर्व देकारदारांकडून या परिपत्रकातील सुधारीत दरांनुसार इसारा अनामत रक्कमेचा परतावा करण्यापूर्वी छाननी शुल्क अनुज्ञेय वस्तू व सेवाकरासहित वसूल करण्याचे अथवा देकारदाराच्या संमतीने इसारा अनामत रक्कमेतून समायोजित करण्यासंबंधीचे निदेश द्यावेत. "

तदनंतर सुधारित परिपत्रक क्र. सीए/एफआरजी/०४ दि. २४.०५.२०२३ निर्गमित करण्यात आले. सदर परिपत्रकात पुढील प्रमाणे निर्देश देण्यात आले आहेत.

"दरपत्रिका/निविदा/दरपत्रिका/ई-दरपत्रिका/ई-निविदा दस्तऐवजांकरिता मा. महानगरपालिका आयुक्तांच्या मंजुरीच्या दिनांकापासून छाननी शुल्क न आकारता, एसआरएम कार्यप्रणाली मध्ये निविदा शुल्क न आकारण्यासंबंधीची कार्यवाही माहिती व तंत्रज्ञान खात्याकडून पूर्ण झाल्यावर त्यानंतरच निविदाकाराकडून छाननी शुल्क आकारण्यात यावेत. तसेच सदर छाननी शुल्काचा भरणा लेखा संकेताक 140402609 - Scrutiny Fees From Tenders (From May 2023)-Taxable यामध्ये करण्यात यावा."

ANNEXURE - VI

परिपत्रक क्र. सीए/एफआरजी/०४ दि. २४.०५.२०२३ मध्ये नमूद केल्यानुसार एसआरएम प्रणाली मध्ये आवश्यक ते बदल माहित व तंत्रज्ञान विभागाकडून दि. २३.०६.२०२३ रोजी पूर्ण करण्यात आले आहेत.

दरम्यान माहिती व तंत्रज्ञान विभागामार्फत परिपत्रक क्र. Dir/IT/F-59 दि. १०.०५.२०२३ निर्गमित करण्यात आले. सदर परिपत्रकामध्ये दि. १५.०६.२०२३ पासुन रु.२५ लाखावरील सर्व निविदा महानगरपालिकेच्या एसआरएम प्रणालीद्वारे न मागविता महाराष्ट्र शासनाच्या महाटेंडर पोर्टलद्वारे मागाविण्याबाबत निर्देश देण्यात आले आहेत. तसेच परिपत्रक क्र. सीए/एफआरजी/०३ दिनांक ११.०५.२०२३ मध्ये इसारा अनामत रक्कमेचा परतावा करण्यापूर्वी छाननी शुल्क, अनुज्ञेय वस्तू व सेवाकरासहित वसूल करण्याचे अथवा देकारदाराच्या संमतीने इसारा अनामत रक्कमेतून समायोजित करण्यासंबंधीचे निदेश देण्यात आले आहेत. तथापि महाराष्ट्र शासनाच्या महाटेंडर पोर्टलवर इसारा अनामत रक्कमेतून समायोजना करण्याची सुविधा नसल्याने पुढील प्रमाणे सुधारित निर्देश देण्यात येत आहेत.

"महाराष्ट्र् शासनाच्या महाटेंडर / एसआरएम प्रणालीद्वारे मागविण्यात येणारे सर्व अनस्टार दरपत्रिका/निविदा/दरपत्रिका/ ई-दरपत्रिका/ ई-निविदा दस्तऐवजांकरिता निविदा शुल्क (Tender Fee) न आकारता सर्व देकारदारांकडून परिपत्रक क्र. सीए/एफआरजी/०३ दिनांक ११.०५.२०२३ मधील सुधारित दरांनुसार छाननी शुल्क (Scrutiny Fee) अनुज्ञेय वस्तू व सेवाकरासहित लिफाफा 'अ' व 'ब' उघडल्यानंतर व लिफाफा 'क' उघडण्याआधी फक्त नागरी सुविधा केंद्रात चलनाद्वारे भरण्यात यावे."

संदर्भित परिपत्रकातील अन्य निर्देशांमध्ये कोणताही बदल करण्यात आलेला नाही.

सही/-१६.१०.२०२३ श्री.पांडुरंग गोसावी प्रमुख लेखापाल (पा.पु.म.नि.)

> सही/-१६.१०.२०२३ श्री. प्रशांत गायकवाड उप. आयुक्त (वित्त) प्र.

सही/-१८.१०.२०२३ श्री. पी. वेलरासू अति.आयुक्त (प्रकल्प)

परिपत्रक

86-2205

क्र.सीए/एफआरजी/१० दिनांक १९.१०.२०२३

प्रतप्रतींसह) यांना माहितीकरिता व पुढील

आवश्यक त्या कार्यवाहीकरिता अग्रेषित.

प्रमुख लेखापाल (वित्त) यांजकरिता

सही/-१६.१०.२०२३

श्री. प्रदिप भा. पडवळ

प्रमुख लेखापाल (वित्त)प्र.

Array 1



ANNEXURE –VII STAMP DUTY REGISTER

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



महाराष्ट्र शासन

मुद्रांक जिल्हाधिकारी अंमलबजावणी -1, मुंबई, यांचे कार्यालय प्रधान मुद्रांक कार्यालय नगर भवन, फोर्ट, मुंबई 400 001.

Tel.No.22664585 Email id cosenf1.mumbai@igrmahrashtra.gov.in Fax.no.22656904

जा.क्र.मू.जि.अमल-1/ 780 / २०२३

दिनांकः - . 2 NOV 2023

प्रति,

Ę

प्रमुख अभियंता (किनारी रस्ता प्रकल्प) म्युनिसिपल अभियांत्रिकी हब इमारत, तिसरा मजला, डॉ.ई. मोझेस रोड,

वरळी नाका, वरळी, मुंबई - 400 018

मुद्रोक जिल्हा महाराष्ट्र मुंद्रांक अधिनियमान्वये मुद्रांक शुल्क वसुलीबाबत. बिषय- महाराष्ट्र मुंद्रांक अधिनियमान्वये मुद्रांक शुल्क वसुलीबाबत. संदर्भ- संदर्भ-1. आपले दि.14/07/2023 रोजीचे पत्र

2.या कार्यालयाचे जा.क्र.396 दि.23/02/2016 रोजीचे पत्र महोदय: जि असत- त

उपरोक्त संदर्भिय पत्र क्रमांक 2 अन्वये आपणास पत्राद्वारे कळविण्यात आले आहे. '' (सीम्रेत पत्राची छायांकित प्रत अवलोकनार्थ जोडली आहे)

प्रानुख अधितसेच (उपरोक्त) विषयांकित प्रकरणी संदर्भ क्र.1 अन्वये आपण कार्यकंत्राटाच्या दसुनिविरील ''बैंकी स्मीपत्र अनुच्छेद 54 (Read with 40(b)) नुसार एकुण रकमेवर 0.5% मुद्रांक शुल्का देयमआहेज तसेचो मुंदतो संपल्यावर बँक हमीपत्राचा कालावधी वाढविण्यात आल्यास ते मविने बैंक हमीपत्री संसजून त्यांवर 0.5% मुद्रांक शुल्क भरणे आवश्यक आहे." या विषयाबाबत अभिप्राय/खुलासा मागविल्ला होता.

त्यास अनुसरुन औपणास कळविण्यात येते की कार्यकर्त्राटांच्या दस्तावरील बॅंक हमीपत्र अनुच्छेद 54 (Read with 40(b)) नुसार एकुण रकमेवर <u>0.3% मुद्रां</u>क शुल्क देय आहे. तसेच मुद्रत संपल्यावर बॅंक हमीपत्राचा कालावधी वाढविण्यात आल्यास ते नविन बॅंक हमीपत्र समजून मुद्दादय त्यावर 0.3% मुद्रांक शुल्क भरणे आवश्यक आहे. तसेच आपण संदर्भित पत्राद्वारे उल्लेखित केलेल्या बाबीबोबर्त खुलासा खालीलप्रमाणे आहे.

	0.1% दरान I
1. उपरोक्त संदर्भाकित जा.क्र/अमल/कार्यकंत्राट/396/2016 कार्यकंत्राटावर तिरोध 30777 दि. 23/02/2016 च्या पत्रानुसार कंत्राटदाराने पूर्वप्रिमाणेच	आंकोरणी
HIGHTEN HEIGH WARES THE THE THE	
Sucon High Car in the second second second	uters é
विंहा बैंक हनीपुत्र कुरावत रहे। मुद्राक शुल्क भरावयाचे आहे.	1. h

रणार जन्म किल्लान प्रयोग अनुस्टेंड 54 (एकलेन प्रथणान भुदल संपल्यानर केल्लान न्यान

लावर 0 3% मुक्ते मुझ लाग

2.	कंत्राटदाराने बॅंक हमीपत्र कालावधी संपण्यापूर्वी बॅंक	बँक हमीपत्र कालावधी
	हमीपत्राची मुदत वादविल्यास, त्यानुसार मुदतवाद	संपण्यापुर्वी बँक हमीपत्राची
	करण्यात आलेल्या बँक हमीपत्राला नविन बँक हमीपत्र	मुदत वाढविल्यास, बॅक
	समजण्यात येऊन कंत्राटदारास मुद्रांक शुल्क भरण्याची	
	आवश्यकता आहे का ?	हमीपत्र समजण्यात येऊन
		कंत्राटदारास त्यावर मुद्रांक
	•	शुल्क भरण्याची आवश्यकर्ता
		आहे.
3.	असल्यास अद्ययावत मुद्रांक अधिनियमामध्ये वाढीव	अनुच्छेद 54 अन्वये
	कालावधीच्या व दुरुस्ती बँक हमीपत्रावर मुद्रांक शुल्क	
	आकारण्याची कोणती तरतूद आहे.	
4.	महाराष्ट्र मुद्रांक कायदा 1958, शेड्युल 1 व शेड्युल	लागू आहे.
	2 चे दि. 20/01/2022 पासूनचे स्धारीत आर्टीकल	(2). 131 . (Ar (Card)
	नं 54 ज्यामध्ये मदांक शल्क बँक हमीपत्राच्या 0.3%	নুয়াত আয়েষ্টালন্দ
	व जास्तीत जास्त रु. 20 लाख असे नमूद केले आहे	t stirt i de beska i P
	ते सद्यस्थितीत लागू आहे किंवा कसे ?	

ूर् सोबत - पत्राची छायांकित प्रत

and the second

्भ्रेप्र्यून्न (एन. एन. राजपूरकर)

मुद्रांक उपअधिक्षक मुद्रांक जिल्हाधिकारी अंमलबजावणी -1



ANNEXURE –VIII LEGAL & STATIONARY CHARGES

Lump sum tender (Turnkey) for construction of Residential Tenements (having size of 37.80 sq m & 55.55 sq m each) on plot known as '600 tenement plot' bearing CTS No. 1(pt) & CTS No. 3 (pt) (Sub plot D having area 8746.90 sq m) at Village Deonar, M/E Ward.



ANNEXURE - VIII बृहन्मुंबई महानगरपालिका विधी खाते

परिपत्रक क्र. २६२०६ दि. 31.08.2023

विषय - कंत्राट करार करण्यासाठी वसूल करावयाचे विधी आकार (Legal charges) व लेखनसाहीत्य आकार (Stationery charges)

संदर्भ – 1. परिपत्रक क्र. 10539 दि. 28.03.2023 2. एमजीसी/एफ/534 दि. 28.08.2023

महानगरपालिकेच्या विविध खात्यांमार्फत मागविण्यात येणा-या निविदांसंदर्भात लेखी करार करताना पक्षकाराकडून एकत्रितरित्या आकारावयाच्या विधी आकार व लेखनसाहित्य आकाराची उपरोक्त संदर्भित क्र. 1 वरील परिपत्रकानुसार दि. 01.04.2023 पासून आकारणी करण्यात आलेली आहे.

तथापि महानगरपालिका आयुक्त यांच्या संदर्भ क्र. 2 च्या मंजुरीनुसार कंत्राट करार करण्यासाठी वसूल करावयाचे विधी आकार (Legal charges) व लेखनसाहीत्य आकार (Stationery charges) यामध्ये सुधारणा करण्यात आली असून खालील तक्त्यामध्ये दर्शविल्याप्रमाणे दि.01.09.2023 पासून सुधारीत विधी व लेखनसाहित्य (एकत्रितरित्या) आकार विहित करण्यात आलेले आहेत.

अनु. क्र	कंत्राट किंमत	एकत्रितरित्या आकारावयाचे सुधारीत विधी व लेखन साहीत्य आकार दि. 01.09.2023 पासून दि. 31.03.2024 पर्यंत
1	रु 50,000/-	निरंक
2	रु. 50,001 ते रु. 1,00,00,000	कंत्राट किंमतीच्या 0.10% दराने (अशी येणारी रक्कम पुढील शंभराच्या पटीत परावर्तीत करणे यासापेक्ष) अधिक 18% दराने वस्तू व सेवाकर (किमान रु. 1000/- अधिक वस्तू व सेवाकर आणि कमाल रु. 10000/- अधिक वस्तू व सेवाकर)
3	रु. 1,00,00,001 ते रु. 10,00,00,000/-	रु. 1,00,00,000/- पर्यतच्या कंत्राट किंमतीसाठी रु.10,000/- अधिक रु. 1,00,00,000/- पेक्षा जास्त रक्कमेवर 0.05% दराने (अशी येणारी रक्कम पुढील शंभराच्या पटीत परावर्तीत करणे यासापेक्ष) अधिक 18% दराने वस्तू व सेवाकर

ANNEXURE - VIII

4	रु. 10,00,00,001 ते पुढील कंत्राट किंमतीसाठी	रु. 10,00,00,000/- पर्यतच्या कंत्राट किमतीसाठी रु.55,000/- अधिक रु. 10,00,00,000/- पेक्षा जास्त रक्कमेवर 0.01% दराने (अशी येणारी रक्कम पुढील शंभराच्या पटीत परावर्तीत करणे यासापेक्ष) अधिक 18% दराने वस्तू व सेवाकर

(शोभा अजितकुमार) उप कायदा अधिकारी (हस्तांतरण -2) विधि खाते

प्रत

(संदिप मो. पाटील) संयुक्त कायदा अधिकारी (प्र.) (शहर दिवाणी न्यायालय) विधि खाते

परिपत्रक क्र.

दि. 31.08.2023

(सुनिर

कायदा अधिकारी

विधि खाते

..... यांना माहीतीकरीता व पुढील

आवश्यक त्या कार्यवाहीकरीता अग्रेषित.

(संदिप मो. पाटील) उप कायदा अधिकारी (आस्थापना) विधि खाते