
















DOOR WINDOW SCHEDULE					
LOCATION	TYPE	NOS	SIZE	DESCRIPTION	
PANTRY, STAFF LOUNGE, STAFF DINING	 D1	15	1.20 X 2.10	SERVICE DOOR, IN STAINLESS STEEL PUF PANELS WITH AUTO CLOSING DOOR CLOSERS WITH VISION PANEL	
SOILED UTILITY, LINEN DECONTAMINATION, AHU, STORE, DRUG RM, CLEAN ROOM, LINEN ROOM	 D1-A	21	1.20 X 2.10	SERVICE DOOR, LAMINATE FINISHED DOORS WITH AUTO CLOSING DOOR CLOSERS WITH VISION PANEL	
EQUIPMENT ROOM	 D1-B	3	0.90 X 2.10	SERVICE DOOR, LAMINATE FINISHED DOORS WITH AUTO CLOSING DOOR CLOSERS WITH VISION PANEL	
FIRE STAIRCASE DOORS	 D2	6	2.00 X 2.10	FIRE RESISTANT DOOR AS PER FIRE NORMS WITH PANIC BARS	
BLANK	—	0	00	—	
WARD DOORS	 D4	63	1.50 X 2.10	HERMATICALLY SEALED STAINLESS STEEL PUF CLEAN DOOR WITH AUTO CLOSING DOOR CLOSERS AND VISION PANEL	
PATIENT ENTRY EXIT MAIN DOORS	 D4-A	6	1.50 X 2.10	HERMATICALLY SEALED STAINLESS STEEL PUF CLEAN DOOR WITH AUTO CLOSING DOOR CLOSERS AND VISION PANEL	
ENTRY TO DOCTOR ROOM, NURSE TOILET, STAFF TOILET, COMMON TOILET, DECONTAMINATION ROOM	 D5	22	0.90 X 2.10	LAMINATE FINISHED, SINGLE LEAF TOILET DOORS WITH AUTO CLOSING DOOR CLOSERS AND TRIM ACCESSORIES TO PREVENT LOSS OF A/C	
DOCTOR ROOM, NURSE TOILET, STAFF TOILET, COMMON TOILET,	 D5-A	38	0.75 X 2.10	LAMINATE FINISHED, SINGLE LEAF TOILET DOORS WITH AUTO CLOSING DOOR CLOSERS AND TRIM ACCESSORIES TO PREVENT LOSS OF A/C	
OPD TOILET MAIN DOOR	 D5-B	2	0.90 X 2.10	LAMINATE FINISHED, SINGLE LEAF TOILET DOORS WITH AUTO CLOSING DOOR CLOSERS AND TRIM ACCESSORIES TO PREVENT LOSS OF A/C	
WARD TOILET DOORS, SERVER ROOM	 D6	21	0.90 X 2.10	SS PUF PANEL, SINGLE LEAF TOILET DOORS (OPENING INTO ROOM) WITH AUTO CLOSING DOOR CLOSERS AND TRIM ACCESSORIES TO PREVENT LOSS OF A/C	
VC ROOM, SAMPLE ROOM	 D7	9	0.90 X 2.10	FROSTED GLAZED DOORS WITH AUTO DOOR CLOSER	
CSSD ROOM INTERNAL DOORS	 D8	4	0.90 X 2.10	SS PUF PANEL, SINGLE LEAF TOILET DOORS (OPENING INTO ROOM) WITH AUTO CLOSING DOOR CLOSERS AND TRIM ACCESSORIES TO PREVENT LOSS OF A/C	
NURSE ROOM, SLUICE ROOM ICU, CLEAN ROOM ICU	 SD1	8	0.90 X 2.10	FROSTED GLAZED SLIDING DOORS, SS PUF DOOR WITH VISION PANEL	
OPD ROOMS	 SD2	5	0.90 X 2.10	FROSTED GLAZED SLIDING DOORS	
WARD WINDOWS	W1	91	1.50 X 1.50	SEALED ALUMINIUM CASEMENT WINDOWS	
SERVICE UTILITY ROOMS	W1-A	58	1.50 X 1.50	OPENABLE ALUMINIUM CASEMENT WINDOWS	
DOCTOR ROOM, SERVER ROOM	W2	67	0.90 X 1.50	FIXED ALUMINIUM CASEMENT WINDOWS	
DRUG ROOM/STORE ROOM	W2 A	3	0.90 X 1.50	OPENABLE ALUMINIUM CASEMENT WINDOWS	
STAIRCASE	W3	13	1.5 X 1.00	OPENABLE ALUMINIUM CASEMENT WINDOWS	
TOILETS	V	49	1.5 X 1.00	FIXED ALUMINIUM CASEMENT WINDOWS	

DRAWING TITLE:-	
DRAWN BY:	SONAL
CHECKED BY:	
APPROVED BY:	G.P.R
SCALE:	NTS
DRG.NO:- FCEL/1252/19-20/KBN15/AR013	R0

CLIENT:- MUNICIPAL CORPORATION OF GREATER MUMBAI

ARCHITECT/STRUCTURAL CONSULTANT:-
 FEMSTRUCT
CONSULTING ENGINEERS LLP.
A1, 304 KALPAK ESTATE, S.M.MARG,
WADALA (EAST), MUMBAI (400 037)
E-MAIL:- femstruct@gmail.com
MOB. :- +91 9766447704

PROJECT:- PROPOSED CONSTRUCTION OF ISOLATION WARD FOR CORONA VIRUS AT KASTURBA HOSPITAL IN E WARD

RELEASED FOR:

CONCEPT SCHEMATIC

ADVANCE COPY APPROVAL

CONSTRUCTION TENDER

REV.	DESCRIPTION	DATE	BY	CHD.	APRD.

REVISION SCHEDULE

SIZE-N